

NOTES:

- 1. PROVIDE (2) 1" EMPTY CONDUITS WITH PULL WIRE FOR FUTURE SATELLITE DISH LOCATED ON ROOF. (1) 1" CONDUIT SHALL BE USED FOR COAX AND (1) 1" CONDUIT SHALL BE USED FOR POWER.
- 2. NOT USED.
- 3. (1) 4" CONDUIT SHALL BE ROUTED FOR CATV SERVICE FROM PROPERTY LINE TO MDF. WHEREVER POSSIBLE, INCOMING SERVICE SHALL BE ROUTED ALONG AT&T CONDUIT SERVICE PATHWAY. PULL ROPE TO BE PROVIDED WITHIN CONDUIT, CONTRACTOR TO PROVIDE COMCAST/AT&T WITH CONDUIT FOOTAGE. COORDINATE ALL WORK WITH COMCAST PRIOR TO INSTALLATION. MAXIMUM OF THREE (QTY. 3) 90 DEGREE SWEEPS ARE ALLOWED BEFORE ADDITIONAL PULL BOXES ARE REQUIRED. FIELD DETERMINE EXACT ROUTING AND LOCATION OF CONDUIT. INDICATE TOTAL LINEAL FOOTAGE OF CONDUIT. SEE SITE PLAN FOR ADDITIONAL INFORMATION.
- 4. (1) 4" CONDUIT SHALL BE ROUTED FOR AT&T SERVICE FROM PROPERTY LINE TO MDF ROOM. PULL ROPE TO BE PROVIDED WITHIN CONDUIT, CONTRACTOR TO PROVIDE COMCAST/AT&T WITH CONDUIT FOOTAGE. COORDINATE ALL WORK WITH AT&T PRIOR TO INSTALLATION. MAXIMUM OF THREE (QTY. 3) 90 DEGREE SWEEPS ARE ALLOWED BEFORE ADDITIONAL PULL BOXES ARE REQUIRED. FIELD DETERMINE EXACT ROUTING AND LOCATION OF CONDUIT. SEE SITE PLAN FOR ADDITIONAL INFORMATION.
- 5. FOR SCHOOL ADDITIONS, PROVIDE (1) 100PR BUILDING TIE CABLE TO NEW IDF AND (1) 100PR BUILDING TIE CABLE TO EXISTING NETPOP, ONLY IF REQUIRED.
- 6. VERIFY EXACT MDF LAYOUT WITH CPS ITS SR. INFRASTRUCTURE MANAGER (773-553-6030).
- 7. RENOVATION PROJECT: PROVIDE ADDITIONAL RACK IF REQUIRED.
- 8. THE FINISHED FLOOR IN THE MDF SHALL BE STATIC DISSIPATIVE.

					CHICAGO PUBLIC SCHOOLS					
					ALA School	CAPITAL	. IMPROVE	MENT PR	OGRAM	
	INFORMATION TECHNOLOGY SERV								RVICES	
	INFRASTRUCTURE STANDARDS							8		
				TYPICAL MDF						
					ROOM PLAN					
1				-	DESIGNED	1			SHEET NO.	
					CPS				SHEET NO.	
					DRAWN CPS					
					CHECKED	PROJECT NUMBER	SCALE	DATE	ED.104	
					CPS	PROJECT NUMBER				
	1		DVS RACK #5		APPROVED CPS	1	NONE	03/30/2016		
	NO.	DATE	REVISION	8Y	~3					